

ADDENDUM NO. 1

DATED

DECEMBER 29, 2017

NATICK, MASSACHUSETTS
BOARD OF SELECTMEN

CONTRACT NO. W-143

SPRINGVALE #4 WATER PUMP STATION

TO ALL BIDDERS OF RECORD:

This Addendum shall be part of the Contract Documents as provided in the Instructions to Bidders of Contract No. W-143. Acknowledgment of receipt of the Addendum shall be made by inserting its number on Page 1 of the General Bid Form and Page 1 of the Field Sub-Bid Form. Failure to do so may subject the bidder to disqualification.

The Voluntary Pre-Bid meeting was held on 12-28-17 with three attendees. Attendance roster is available upon request.

Section 00510 Agreement page 1 Article 3 Contract Time, 3.1: **Insert the following after 3.1**

“A. Interim Completion Date: In order to allow the second re-use tank (under separate contract) to be placed into service, the underground gravity sewer, sludge water line to backwash tank, piping vault and electrical valve control panels must be installed and operational by May 15, 2018. The Liquidated Damage clause in paragraph 3.2 apply to the interim completion date.”

Section 00800 page 11 & 12 Paragraph 5.04-B-2.a

Change limits for Worker's Compensation and Employer's Liability to the following.

Employer's Liability - Each Accident:	\$1,000,000
Employer's Liability – Disease Policy Limits:	\$1,000,000
Employer's Liability - Each Employee:	\$1,000,000

Section 05500 Metal Fabrication:

Delete: “Filed Sub-Bid Required” at the top of the page.

Drawing A1: Roof slope on building is 2” front to back by sloping the cast-in place concrete wall cap. Optional construction of roof slope is the installation of a level cast-in-place concrete wall cap and roof planks and the creation of the 2” slope with the insulating board, maintaining the specified minimum thickness at the rear of the building.

ADDENDUM NO. 1

Page 1 of 3

Drawing A1 Left Wall (East) and Right Wall (West) details:

Add Control Joint in both walls near corner.

Drawing E8: Top left detail “PROPOSED TANK NO.2 SUPERNATANT”:

Add the word “OWNER” after the words “FURNISHED BY” in the detail callout

Drawing E2 LIGHTING AND SECURITY FLOOR PLAN detail:

Add a Fire Alarm Panel next to the Intrusion Panel and install 120-Volt power source and signal cable to SCADA panel. All Smoke and Heat sensors to be connected to the Fire Alarm Panel.

Drawing E2 LIGHTING AND SECURITY FLOOR PLAN detail:

Add a Fire Alarm Pull station next to the Intrusion Panel and install required conduits and conductors for connection to Fire Alarm Panel.

Drawing E2 LIGHTING AND SECURITY FLOOR PLAN detail:

Delete the “Co2” units from the detail. Co2 units not required for project.

Drawing E2 SPRINGVALE #4 PROPOSED INTRUSION DETECTION SYSTEM detail:

Delete proposed carbon monoxide detectors and proposed heat/smoke detectors from detail. Heat/Smoke units will connect to proposed fire alarm panel. CO sensors not required for project.

