

ADDENDUM NO. 2

DATED

JANUARY 2, 2018

NATICK, MASSACHUSETTS
BOARD OF SELECTMEN

CONTRACT NO. W-143

SPRINGVALE #4 WATER PUMP STATION

TO ALL BIDDERS OF RECORD:

This Addendum shall be part of the Contract Documents as provided in the Instructions to Bidders of Contract No. W-143. Acknowledgment of receipt of the Addendum shall be made by inserting its number on Page 1 of the General Bid Form and Page 1 of the Field Sub-Bid Form. Failure to do so may subject the bidder to disqualification.

Drawing G2: See revised plan view for G2 drawing attached.

1. Added proposed underground electrical conduit and conductors to proposed piping vault and re-use tank. General Contractor to install conduits, Electrical Contractor to furnish conduits and furnish and install conductors.
2. Existing ground elevations added to revised G2 plan view attached; existing electrical manhole in driveway, near corner of existing flow meter vault, near existing observation well and near existing Pump Station No. 4 building.

Drawing G2: A section of the 16" CI abandoned drain will require cutting and removal to facilitate the 6" sewer pipe installation. Contractor to cut 16" pipe and install brick and mortar to close up both cut ends.

Drawing G2: Proposed 6" PVC sewer pipe will cross 20" DI Treated and 20" DI Filtered water pipes, depths are unknown. Contractor to test pit to determine pipe depths prior to installation of 6" sewer pipe leaving proposed pump station.

Drawing G2: Eliminate call out for "Silt Sock" – none required for project.

Drawing A4: **Delete "Roof Plank Lifting Lug & Anchor Details"** – none required for project.