

ADDENDUM NO. 3

DATED

APRIL 20, 2018

NATICK, MASSACHUSETTS
BOARD OF SELECTMEN

CONTRACT NO. W-148

WEST CENTRAL, ROUTE 30 WATER MAINS AND
HEALTH CENTER FORCEMAIN

TO ALL BIDDERS OF RECORD:

This Addendum shall be part of the Contract Documents as provided in the Instructions to Bidders of Contract No. W-148. Acknowledgment of receipt of the Addendum shall be made by inserting its number on Page 00300-1 of the Bid Form. Failure to do so may subject the bidder to disqualification.

Clarification Statement: House #281 & 283 West Central Street are new construction houses with new water services installed across the roadway to the 6" water main. Work under this contract will not require replacement of the two water services. It will require reconnection of the PE water service to the new 8" water main.

Ledge Statement: During the installation of the new water services for House #381 & 283 ledge around the 6" water main was observed. The ledge required a jack hammer to remove the ledge to allow tapping the 6" water main for the new corporations. With this information we are adding a ledge removal quantity. The ledge item will provide compensation for mechanical removal of the ledge under and on each side of the 6" water main to facilitate the installation of the 8" water main. The locations that may have ledge is between STA 34+00 to 4+00.

Section 00300 BID

Items have been revised per Addendum No. 2 and the addition of a ledge item.

Delete pages 00300-1 through 00300-25 and **Insert** the attached pages 00300-1 through 00300-25.

Section 00510 Agreement, Page 4

Insert the following after Contract Item No. 49.

"50. For Ledge Removal 66 C.Y. \$ _____ \$ _____"

Section 01025 Measurement and Payment, Page 4

Insert the following after Contract Item No. 49.

“50. Ledge Removal”

Section 01025 Measurement and Payment, Page 24

Insert the following after Par. 1.46.B.2.

“1.46 ROCK EXCAVATION WITHOUT EXPLOSIVES (ITEM 50)

A. Measurement

1. Ledge encountered within the trench, which can be removed and disposed of without heavy ripping or use of a power hammer shall be removed and measured on the surface in three dimensions to determine volume.
2. If ledge removal is required to provide a minimum of 12” on each side and 6” below the new 8” water main, valves, fittings and taps, will be paid as measured in the trench.

B. Payment

1. Payment for ledge excavation requiring heavy ripping by the excavator or power hammer shall be made at the unit contract price per cubic yard under Item No. 50 in the Agreement. The unit price shall be full compensation for all costs associated with ledge excavation and disposal.
2. Disintegrated rock which can be removed without the use of heavy ripping or power hammer and boulders smaller in volume than one (1) cubic yard will not be considered for payment under this item, and shall be classified as earth excavation.
3. Broken ledge from previous blasting operations, removed without heavy ripping or power hammer will be considered earth excavation and all costs associated will be paid for under the various pipe item.”